

TECHNICAL DATA SHEET

Design | Manufacture | Supply

Hopton Street Herringbone Harbour Collection

16/6x100x600mm / Unfinished / Distressed / Skipsawn / Natural Grade / Herringbone



INSTALLATION METHODS

Fully Bonded	Yes (recommended)
Nailed	Yes
Floated on underlay	Yes
Over Underfloor Heating	Yes (see below*)

*The underfloor heating system must have an even temperature over the entire floor surface. The sub floor temperature that the floor boards are sitting on cannot exceed 27°c. The heating system must be working two weeks prior to install. Once the floor is installed, acclimatise the wood flooring by turning the heating temperature up 1°c per day (18-27°c) then back down 1°c per day. This is to not shock the wood, which can cause cracking and shrinking.

GRADING CRITERIA

Natural grade includes variations in colour tone from plank to plank, with more noticeable markings such as knots, streaks, sapwood and fine cracks. The grading is perfect for owners who want a non-uniform, natural wood floor.

PRODUCT DETAILS

ils
tions and materials are available

INSTALLATION AND WARRANTY

All JackEvie Wood Floor Collections floor must be installed by a competent installer who will have the necessary skills and take individual site circumstances into account. JackEvie Wood Floor Collections warranty only applies to floors which have been installed by a competent flooring installer comparable to BS8201 in the UK or equivalent standards worldwide.

This technical data sheet was written by JackEvie Wood Floor Collections. At the time of writing and publication of the sheet, all information is specified correctly. The company reserves the right to change the specifications of this product at any time without prior notice to third parties. The photographs use in the sheet are intended only as illustrations. No rights can be derived from them.