

TECHNICAL DATA SHEET

Design | Manufacture | Supply

Mackenzie Square Herringbone Loggerheads Collection

15/4x120x500mm / Unfinished / Brushed / Distressed / Sawn Marked / Rustic Grade / Herringbone



INSTALLATION METHODS

Fully Bonded	Yes (recommended)
Nailed	Yes
Floated on underlay	Yes
Over Underfloor Heating	Yes (see below*)

*The underfloor heating system must have an even temperature over the entire floor surface. The sub floor temperature that the floor boards are sitting on cannot exceed 27°c. The heating system must be working two weeks prior to install. Once the floor is installed, acclimatise the wood flooring by turning the heating temperature up 1°c per day (18-27°c) then back down 1°c per day. This is to not shock the wood, which can cause cracking and shrinking.

GRADING CRITERIA

Rustic grade oak comes with all the variations and authentic characteristics familiar with this grade of wood. Featuring colour variations, grain pattern variations, unlimited knots size, cracks and splits.

PRODUCT DETAILS

aff for details
bur)
n Marked
cus Robur)
vood
nce instructions and materials are available

INSTALLATION AND WARRANTY

All JackEvie Wood Floor Collections floor must be installed by a competent installer who will have the necessary skills and take individual site circumstances into account. JackEvie Wood Floor Collections warranty only applies to floors which have been installed by a competent flooring installer comparable to BS8201 in the UK or equivalent standards worldwide.

This technical data sheet was written by JackEvie Wood Floor Collections. At the time of writing and publication of the sheet, all information is specified correctly. The company reserves the right to change the specifications of this product at any time without prior notice to third parties. The photographs use in the sheet are intended only as illustrations. No rights can be derived from them.